# Detailed Information

| Part Number | Description | Qty |
|---|---|---|
| GMKG150 | KG150 Generator System | |
| KG150-CP1 | KG150 Generator Set | 2 |
| | **Includes the following:** | |
| | Literature Languages | English |
| | Approvals and Listings | UL2200 Listing/cUL Genset List |
| | Engine | SnglFuel,UL,PreAlarm,NG,Stdby |
| | Nameplate Rating | Standby 130C Rise |
| | Voltage | 60Hz, 120/208V, Wye, 3Ph, 4W |
| | Alternator | 4S12X |
| | Cooling System | Unit Mounted Radiator, 50C |
| | Skid and Mounting | Skid, 53" |
| | Air Intake | Standard Duty |
| | Controller | APM402 |
| | Enclosure Type | Sound |
| | Enclosure Material | Steel |
| | Starting Aids, Installed | 1500W,120V |
| | Electrical Accy.,Installed | Battery, 1/12V, Wet |
| | Electrical Accy.,Installed | Battery Charger, 10A |
| | Electrical Accy.,Installed | Run Relay |
| | Electrical Accy.,Installed | 2 Input/5 OutputModule |
| | Rating, LCB 1 | 80% Rated |
| | Amps, LCB 1 | 600 |
| | Trip Type, LCB 1 | Electronic, LI |
| | Interrupt Rating LCB 1 | 35kA at 480V |
| | Miscellaneous Accy,Installed | Coolant in Genset |
| | Warranty | 5 Year Comprehensive |
| | Testing, Additional | Power Factor Test,0.8,3Ph Only |
| PA-343303 | Gaseous Fuel Filter | 2 |
| GM13706-KP2 | Flexible Fuel Line (Nat/LP) | 2 |
| GM114021-KP | Lit Kit, KG150 General Maintenance | 2 |