

KG200 Generator Set

Includes the following:

Literature Languages	English
Approvals and Listings	UL2200 Listing/cUL Genset List
Engine	SnglFuel,UL,PreAlarm,NG,Stdbby
Nameplate Rating	Standby 130C Rise
Voltage	60Hz, 120/208V, Wye, 3Ph, 4W
Alternator	4S13X
Cooling System	Unit Mounted Radiator, 50C
Skid and Mounting	Skid, 53"
Air Intake	Standard Duty
Controller	APM603
Enclosure Type	Sound
Enclosure Material	Steel
Starting Aids, Installed	1500W,120V
Electrical Accy.,Installed	Battery, 1/12V, Wet
Electrical Accy.,Installed	Battery Charger, 6A
Electrical Accy.,Installed	Run Relay
Rating, LCB 1	100% Rated
Amps, LCB 1	800
Trip Type, LCB 1	Electronic, LSI
Interrupt Rating LCB 1	35kA at 480V
Miscellaneous Accy,Installed	Coolant in Genset
Miscellaneous Accy,Installed	Rodent Guards
Warranty	Standard
Testing, Additional	Power Factor Test,0.8,3Ph Only
Total unit length in inches	172
Total unit width in inches	54
Total unit height in inches	83
Total unit weight (lbs)	5,157
Weight/Dimensions Disclaimer *	Estimates-Not for Construction